


15-169-00631-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Saline County, Sec. 19 Twp. 15 Rge. 3 (E) W (W)
Location as "NE/CNW/KSW" or footage from lines App S/2 S/2 SW
Lease Owner Midwest Supply Company
Lease Name Richter Well No. 5
Office Address 343 Marmaton Road, El Dorado, Ks 67042
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed February 20 19 53
Application for plugging filed April 3 19 74
Application for plugging approved April 5 19 74
Plugging commenced June 5 19 74
Plugging completed June 7 19 74
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well 3403 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	300'	none
				5 1/2"	3398.5'	3006.52'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Rig up and dig out cellar. Filled with sand to 3350' and added 5 sacks of cement to plug to bottom. Put a 10' rock bridge at 210' to 200' and added 25 sacks of cement. Put a 10' rock bridge at 40' to 30' and added 10 sacks of cement to plug to surface.

RECEIVED
STATE CORPORATION COMMISSION
JUN 26 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor THE BUCKEYE CORPORATION
Address Box 1020, El Dorado, Kansas 67042

STATE OF KANSAS, COUNTY OF BUTLER
Charles V. Cross (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 1020, El Dorado, Ks 67042
(Address)

SUBSCRIBED AND SWORN to before me this 22nd day of June 19 74

My commission expires June 30, 1975
Butler County, Ks.
STATE NOTARY PUBLIC
ISA L. FISHER

ISA L. FISHER
STATE NOTARY PUBLIC
Butler County, Ks.
My Commission Expires
June 30, 1975

Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

COPY

15-169-00631-00-00

Company- JOHN E. PAGE, STUDNICKA ET AL

SEC. 19 T. 15 R. 3W

Farm- Richter No. 5

110' N C S/2 S/2 SW

Total Depth. 3403'

County Saline

Comm. 11-7-52


Comp. 11-21-52

KANSAS

Shot or Treated.

Contractor. E. K. Carey

Issued. 8-15-59



CASING:

8 5/8" 300' cem w/250 sx.

5 1/2" 3398 1/2' cem w/50 sx.

Elevation. 1289' RB

Production. 159 BOPD & VSSW

Figures indicate Bottom of Formations.

Base of Cellar & K.B.	8
clay	22
sand	40
shale & shells	120
shale & lime	250
sand	255
lime & shale	470
lime	700
lime & shale	950
shale & lime	990
salt & shale	1025
shale & lime	1630
lime & shale	1675
lime	2140
lime & shale	2225
lime	2755
shale & lime	2795
shale	2843
lime	3170
shale	3303
lime	3335
shale & lime	3340
shale	3397
lime	3399 RTD
lime	3403
Total Depth	

TOPS:

Mississippi Lime	2842
Base Mississippi Lime	3171
Misner Sand	3303
Hunton (scout)	3307
Maquoketa Shale	3327
Maquoketa Dolomite	3397

RECEIVED
STATE CORPORATION COMMISSION
APR 1 1 1974
CONSERVATION DIVISION
Wichita, Kansas