

15-169-00467-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above Section Plat

Saline County, Sec. 19 Twp. 15 Rge. 3 W (E) (W)
Location as "NE/CNW/SW" or footage from lines C N/2 NW/4
Lease Owner Saline Basin Petroleum Co.
Lease Name Rayce Well No. 1
Office Address 119 South Santa Fe, Salina, Kansas 67401
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 4-27-62
Application for plugging filed II-17-73
Application for plugging approved II-19-73
Plugging commenced II-20-73
Plugging completed II-29-73
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well 3438' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"		2858'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged off bottom of hole with sand. Sand from 3438' to 3400'. Dumped 3 sx of cement. Mudded hole to 265'. Made 15' of rock bridge. Dumped 25 Sx cem. Mudded hole to 40'. Made 10' of rock bridge. Dumped 10 sx of cement, filling to the bottom of the cellar.

RECEIVED
STATE CORPORATION COMMISSION
DEC 3 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address 2809 King St. Hutchinson, Kansas 67501


STATE OF Kansas COUNTY OF Reno ss.
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb
2809 King St. Hutchinson, Kansas 67501
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of November, 1973

My commission expires January 25, 1974

Judy Lamb
Notary Public.



DRILLING LOG ---- ROYCE #1

15-169-00467-00-00
 Location: C N/2 NW/4 (C N/2 NW/4)
 Section: 15-3W (19/15-3W)
 Saline County, Kansas
 Farm: Royce #1
 Well Owner: F. W. Vishnefske
 Contractor: White & Ellis Drig., Inc.
 Started: 4/18/62
 Completed: 4/27/62

Casing Record

8 5/8 (321 Feet) 321' Cemented
 w/210 sacks
 4 1/2 .. (3437 Feet) 3437' Cemented
 w/75 sacks

T.D. (3438 Feet) 3438'
 Kelly Bushing Measurement 5' above ground level.

FORMATION	DEPTH
Soil	0-60
Shale & Lime	320
Lime	321
Lime w/Shale stks.	855
Lime	950
Shale & Shells	1360
Shale & Lime stks.	2230
Lime	2310
Lime & Shale stks.	2425
Shale	2470
Shale & Lime stks.	2700
Shale	2842
Lime	3183
Lime & Shale stks.	3270
Shale & Lime stks.	3412
Dolomite	3438

TOPS

Kansas City	2240
Mississippi	2842
Maquoketa	3408

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 19 1973
 CONSERVATION DIVISION
 Wichita, Kansas

Saline Basin Petroleum Co.
 F. W. Vishnefske - Owner
 119 South Santa Fe
 Salina, Kansas 67401

Office Phone -- 823-2717
 Res. 823-6602