


15-169-19115-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Saline County, Sec 13 Twp. 15S Rge. 3 (E) W (W)
Location as "NE/CNWSW" or footage from lines 100' N C W/2 SW SE
Lease Owner Midwest Supply Company
Lease Name John W. Muir Well No. 1
Office Address 343 Marmaton Road, El Dorado, Ks 67042
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed August 19 19 50
Application for plugging filed March 9 19 74
Application for plugging approved March 12 19 74
Plugging commenced June 12 19 74
Plugging completed June 13 19 74
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes
Name of Conservation Agent who supervised plugging of this well Mr. Gilbert Toman

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 266 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13 3/8"	120'	none
				9 5/8"	275'	none
				7"	3254'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Rig up and dig out cellar. Casing parted 1st joint. Halliburton Cementing pumped 120 sacks of cement to plug well to surface.

RECEIVED
STATE CORPORATION COMMISSION
JUN 26 1974
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor THE BUCKEYE CORPORATION
Address BOX 1020, El Dorado, Kansas 67042

STATE OF KANSAS, COUNTY OF BUTLER, ss.
Charles V. Cross (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Charles V. Cross*
Box 1020, El Dorado, Ks 67042
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of June, 1974

ISA L. FISHER
STATE NOTARY PUBLIC
Butler County, Ks.
My Commission Expires
June 30, 1975

Notary Public.

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY
15-169-19115-00-01

Company- LOREN W. HALLAM ET AL
Farm- John W. Muir No. 1

SEC. 13 T. 15 R. 3W
Approx. 100' N. of
Center of W/2 SW SE

Total Depth. 3266
Comm. 8-5-50 Comp. 8-19-50
Shot or Treated.
Contractor. E. K. Carey
Issued. 11-28-53

County Saline KANSAS



CASING:
13 3/8" 120' cem. w/150 sx cem. circ.
9 5/8" 275' cem. w/250 sx
7" 3254' 12' off bottom cem. w/75 sx

Elevation. 1267 DE

Production. 35 bbls. oil & 100' NW

Figures indicate Bottom of Formations.

Figures indicate bottom of formation K.B.

rotary table, base
of cellar 8
gunbo 10
sand 65
shale & shells 198
lost circulation at 198
lime & shale 275
lime 290
shale & lime 1575
shale 1605
lime 1855
lime & shale 2050
shale 2092
lime 2450
shale 2730
lime 2986
shale 3138
lime 3190
shale 3254
Viola lime 3266
Rotary Total depth

Geologist Tops:
Lansing-KC 2081
Base Kansas City 2423
Cherokee shale 2574
Mississippi 2820
Kinderhook shale 2998
Hunton 3137
Maquoketa shale 3183
Maquoketa dolomite 3254

DST 3255 to 3266, tool open two hours. Recovered 80' oil & 10' heavily cut mud. Ten minutes B.H.P. 90#.

Medical Supply Co
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAR 12 1974
CONSERVATION DIVISION
Wichita, Kansas

TOM BROWN, ETAL #1 MUIR 13-15-3W NW-SW-SE
SALINE County

e1267 Comm. 2-10-61 IP 25 BOPD CORRECTED CARD

Tops	Depth	Datum
LANS	2083	-816
MISS	2720	-1453
KIND	2995	-1728
HUNT	3130	-1863
MAQ	3186	-1919
TD	3266	-1999

Casing 2-17-61
13" 120 OWWO: ORIG COMP BY
9" 290 HALLAM, ETAL FOR 35
7" 3254 BOPD, 9-8-50
SEE OLD CARD FOR DST'S
NEW INFORMATION
MIRT: CO 3244: SET 4" 3244: CO
3262: PB TD: OTD 3266: FU 425'
O & 230' W (FROM OPEN HOLE 3244-
62) FRAC: SWB HOLE FOR 8 HR, NO
TESTS REPORTED: POP
MENTOR POOL PMP EST 25 BO & 15
BOPD
(CORRECTED SECTION
SHOULD BE 13 INSTEAD
DE 11)