


15-169-00063-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

WELL PLUGGING RECORD

Saline County. Sec. 13 Twp. 15S Rge. 3W (E) (W)  
Location as "NE/CNW/SW" or footage from lines NE SE NW  
Lease Owner Ben F. Brack Oil Company, Inc.  
Lease Name Commerford Well No. 3  
Office Address 309 Brown Building, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed 6-14-55 19  
Application for plugging filed 6-14-55 19  
Application for plugging approved 6-14-55 19  
Plugging commenced 6-14-55 19  
Plugging completed 6-14-55 19  
Reason for abandonment of well or producing formation dry hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes, verbally

Name of Conservation Agent who supervised plugging of this well Ruel Durkee  
Producing formation None Depth to top Bottom Total Depth of Well 3475' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Soil, sand, Shale & Shells		0	246	8-5/8"	246	None
Mississippian		2720	2855			
Hunton		3134	3166			
Maquoketa		3250	3262			
Simpson		3429	3456			
Arbuckle		3465	3471			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud, set plug at 190' with 20 sax cement, put 55 sax cement on plug at top of surface pipe, leveled location.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ben F. Brack Oil Company, Inc.  
Address 309-10 Brown Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Bernard D. Grant (employee of owner) or (owner/producer) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bernard D. Grant

309 Brown Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 17th day of June 19 55

Arthur Crist

Notary Public.

My commission expires June 11, 1959



PLUGGING  
FILE SEC 13 T 15 R 34  
BOOK PAGE 22 LINE 14

RECEIVED  
CORPORATION COMMISSION  
JUN 21 1955  
CONSERVATION DIVISION  
Wichita, Kansas

15-169-00063-00-00

BEN F. BRACK OIL COMPANY, INC.  
309-10 BROWN BUILDING  
WICHITA 2, KANSAS

COMMERFORD #3

NE SE NW

Sec. 13-15B-3W  
Saline County, Kansas  
Commenced: 6-2-55  
Completed: 6-14-55

TOTAL DEPTH: 3475'  
ELEVATION: 1261' DF  
1259' Gr

WELL LOG

Surface Soil	0 -	30'
Sand		70
Shale & Shells		155
Sand & Shale		180
Shale & Shells		246
Lime & Shale		1035
Shale & Shells		1380
Lime & Shale		1830
Lime		1910
Shale & Lime		2120
Lime & Shale		2245
Lime		2325
Shale & Lime		2460
Lime & Shale		2570
Shale & Lime		2780
Mississippi Lime		2890
Mississippi Lime & Chert		2955
Lime & Shale		3005
Kinderhook Shale		3065
Shale		3140
Lime		3145
Lime & Shale		3197
Maquoketa Shale		3260
Lime		3339
Lime & Shale		3355
Lime		3401
Limpson		3453
Lime		3470
Arbuckle		3475' T.D. D. & A.

The above depths denote bottom of formations.

CASING

8 5/8"                      246'

To the best of my knowledge, the above is a true and correct statement of the depths and formations and where found.

BEN F. BRACK OIL COMPANY, INC.

By Bernard W. Grant

STATE COMMISSIONER OF GEOL.

JUN 23 1955

CONSERVATION DIVISION  
Wichita, Kansas

**PLUGGING**  
WELL SEC. 13 T. 15 R. 34  
BOOK PAGE 127 LINE 14

WITNESSED:

Gertrude Crist

June 17, 1955.