


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Saline County. Sec. 34 Twp. 15 Rge. 3 (E) W (W)
Location as "NE/CNWxSWx" or footage from lines SW SW NE
Lease Owner Don McKeller, Oil Operator
Lease Name Miller Well No. 1
Office Address Salina, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19____
Application for plugging filed 19____
Application for plugging approved 19____
Plugging commenced 10-5-62 19____
Plugging completed 10-9-62 19____
Reason for abandonment of well or producing formation Depleted.

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3301 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	300'	None
				4-1/2"	3299'	2799'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3301', sanded to 3285' and dumped 4 sacks of cement @ 3285' with dump bailer. Pulled 4 1/2" casing. Bailed fluid to 215', set rock bridge to 200' and ran 3 yards of ready-mix cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING COMPLETE.

NOV 5 1962


CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of October, 1962



Milton J. Volin
Notary Public.

15-169-19082-00-00

DON MCKELLAR
812 Hancock St.
Salina, Kansas

Miller No. 1
Commenced RD: 3/5/61
Completed RD: 3/14/61
Total Depth: 3,301'
Casing: 300' of 8 5/8" 8 rd. thd.
3299' of 4 1/2" Oil String

Sec. 34-15-3W
Saline County, Kansas
Elevation:
Contractor: DUKE BURT
DRILLING CO.

Strata	Depth
Surface Clay & Gyp	0- 40'
Shale & Shells	40- 220
Shale & lime	220- 300
Lime & Shale	300-1695
Shale	1695-1900
Shale & Sand	1900-2090
Shale & Lime	2090-2165
Lime	2165-2230
Shale & Lime	2230-2535
Lime	2535-2640
Lime & Shale	2640-2770
Shale	2770-2787
Lime & Shale	2787-2862
Lime, shale & Chert	2862-2930
Lime	2930-3050
Shale & lime	3050-3296
Maquoketa Dolomite	3296-3301

RECEIVED
STATE CORPORATION COMMISSION
NOV 1 1962
CONSERVATION DIVISION
Salina, Kansas

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

DUKE BURT DRILLING CO.

By *Duke C. Burt*

Signed and Sworn to in my presence this 18th day of March, 1961.

Notary Public

My Commission Expires: September 29, 1963