

15-169-19090-00-00

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

FEB 8 1962  
02-08-1962  
CONSERVATION DIVISION  
Wichita, Kansas

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Saline

Location: CE/2- SE- SE- Sec. 21 Twp. 16 Rge. 3 (W) 1 (W)

Name of Field: Lindsborg Total Depth: 3360'

I have this date completed supervision of plugging of:

Lease Name: Helberg Well No. I

Operator's Full Name: Frank J. Black

Complete Address: P.O. Box 150, McPherson Kansas.

Plugging Contractor R.D. Casing Pulling Co.

Address: Box 569, Ellinwood Kansas License No. 236

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 2:PM Day 2 Month 1 Year 62

The above well was plugged as follows:

Filled hole w/ sand from T:D. 3360' back to 3325' ran 7 sax cement w/ dump bailer.  
Shot off and pulled 7" Casing. Filled hole w/ mud from 3300' back to 240' set a 10' rock  
bridge and ran 25 sax cement. Filled hole w/ mud from 180' back to 40' set a bridge and  
8 sax cement back to zero 5' below ground level. 10 3/4" surface pipe 5' below ground level.

Signed: [Signature]  
Conservation Division Agent

Reviewed: [Signature]  
Field Supervisor

Remarks:

INVOICED  
DATE 2/8/62  
INV. NO. 4523-W