

15-169-20004-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAY 17 1967
05-17-1967
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name V. P. De Weese, Sr.

Complete Address: 900 N.W. Third St., Abilene, Kansas

Lease Name Rueben Anderson Well No. 1

Location C SE NE Sec. 7 Twp. 16 Rge. 3 (E) (W) X

County Saline Total Depth 3465'
3485'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Blackstone Drilling, Inc.

Address: Box 455, Mc Pherson, Kansas License No.

Operation Completed: Hour 7 PM Day 12 Month May Year 1967

The Above well was plugged as follows:

Hole filled with mud to 325'. Plug and $\frac{1}{4}$ sack hulls pushed to 325' and hole cemented
with 25 sacks through drill pipe. Hole filled with mud to 40'. Plug and $\frac{1}{2}$ sack hulls
pushed to 40' and hole cemented to base of cellar with 10 sacks.
Rathole bridged, and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 5/17/67
INV. NO. 5240-W

Signed: *William J. Loman*
Well Plugging Supervisor