

15-169-00473-00-00

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock

Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 4 1969  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Cal Jones

Complete Address: Box 5 Canton, Kansas 67428

Lease Name Carlin Well No. # 2

Location C SE NW Sec. 24 Twp. 15 Rge. 3 (E) / (W)

County Saline Total Depth 3467'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Art Lamb Casing Pulling Co.

Address: Hutchinson, Kansas License No. # 440

Operation Completed: Hour 4 PM Day 2 Month 6 Year 69

The Above well was plugged as follows:

8 5/8"-278'-Circulated w/cement. 5 1/2"-3421'-Cemented. Sand hole to 3400'.

5' Sax.cement 3400' to 3350'. Mud 3350' to 260'. Bridge 260' to 250'.

25' Sax.cement 250' to 175'. Mud 175' to 40'. Bridge 40' to 30'.

10' Sax.cement 30' to 0. Pulled 2750'-5 1/2"-pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 6/4/69

INV. NO. 9882-W