

TO: STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-001-28187-00-01

Spot: S2S2SWSE NE Sec/Twnshp/Rge: 23-25S-19E

2860 feet from S Section Line, 1980 feet from E Section Line

Lease Name: COLTRANE

Well #: R 21

County: ALLEN

Total Vertical Depth: 888 feet

Operator License No.: 5150

Op Name: COLT ENERGY INC

Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF		20		
SURF	6.25	21		6 SX
PROD	2.875	888		90 SX

Well Type: EOR

UIC Docket No: E10334.103

Date/Time to Plug: 01/19/2012 12:00 AM

Plug Co. License No.: 5491

Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP

Proposal Rcvd. from: REX R. ASHLOCK

Company:

Phone: (620) 365-3111

Proposed Plugging Method: RIH W/1" TGB TO BTM, FILL CSG W/CEMENT, POOH, "TOP OFF" CSG W/CMT THEN PRESSURE SQUEEZE CMT, SHUT WELL IN, RETURN AT A LATER DATE, CUT OFF CSG BELOW PLOW DEPTH

Plugging Proposal Received By: STEVE KORF

WitnessType: NONE

Date/Time Plugging Completed 01/19/2012 8:00 AM

KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe inside 2 7/8" casing to TD. Pumped and circulated cement through the 1" pipe inside the 2 7/8" casing from TD to surface. Pulled the 1" pipe. Hooked onto casing and squeezed with cement and shut in well under pressure. A total of 36 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
849	876		

RECEIVED

FEB 15 2012 RMD

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed

[Signature]
(TECHNICIAN)

cc to MIC 2/17/12

RECEIVED

Form CP-2/3

FEB 17 2012

2/20/12

KCC WICHITA