

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-001-28719-00-00
Spot: E2NWSE Sec/Twnshp/Rge: 14-25S-19E
1980 feet from S Section Line, 1540 feet from E Section Line
Lease Name: CONGER Well #: 33
County: ALLEN Total Vertical Depth: 902 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	20		5 SX
PROD	2.875	897		120 SX

Well Type: EOR UIC Docket No: E10334.113 Date/Time to Plug: 01/23/2012 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: REX ASHLOCK Company: Phone: (620) 365-3111

Proposed Plugging Method: RIH W/ 1' TGB TO BTM, FILL CSG W/ CEMENT, POOH, "TOP OFF" CSG W/ CEMENT, THEN PRESSURE SQUEEZE CEMENT, SHUT WELL IN, RETURN @ A LATER DATE, CUT OFF CSG BELOW PLOW DEPTH.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed 01/23/2012 9:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" down the inside of the 2 7/8" casing to TD. Pumped and circulated cement through the 1" pipe inside the 2 7/8" casing from TD to surface. Pulled 1" up to 450' and circulated cement from 450' to surface. Pulled the rest of the 1" out and topped well off with cement. Hooked onto casing and squeezed with cement and shut well in with #500 of pressure. A total of 34 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
846	858		SQUIRREL

RECEIVED

FEB 15 2012 RMD

KCC Chanute Dist #3

Remarks:

Plugged through: TBG

District: 03

Signed

[Signature]
(TECHNICIAN)

cc to MIC-2/17/12

RECEIVED

Form CP-2/3

FEB 17 2012

2/20/12

KCC WICHITA