

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-001-26725-00-00
Spot: N2NESENE Sec/Twnshp/Rge: 23-25S-19E
3740 feet from S Section Line, 220 feet from E Section Line
Lease Name: KNOX Well #: RW 28
County: ALLEN Total Vertical Depth: 873 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	6.25	24		
PROD	2.875	873		

Well Type: EOR UIC Docket No: E10334.14 Date/Time to Plug: 01/19/2012 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: REX R. ASHLOCK Company: Phone: (620) 365-3111

Proposed Plugging Method: RIH W/1" TGB TO BTM, FILL VSG W/CMTN, PHHO, "TOP OFF" CSG W/MT, THEN PRESSURE SQUEEZE CMT, SHUT WELL IN, RETURN AT A LATER DATE, CUT OFF CSG BELOW PLOW DEPTH.

Plugging Proposal Received By: RYAN DULING WitnessType: NONE
Date/Time Plugging Completed 01/19/2012 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe down the inside of the 2 7/8" casing to TD. Pumped and circulated cement through the 1" pipe inside the 2 7/8" casing from TD to surface. Pulled the 1" pipe. Topped well off with cement. Hooked onto the casing and squeezed with cement and shut well in under pressure. A total of 34 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
853	860		SQUIRREL
844	848		SQUIRREL

RECEIVED

FEB 15 2012 RMB

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed

Ryan Duling
(TECHNICIAN)

cc to UIC 2/17/12

RECEIVED

Form CP-2/3

FEB 17 2012

2/20/12

KCC WICHITA