

TO:  
STATE CORPORATION COMMISSIO  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 6720

API Well Number: 15-001-27220-00-00  
Spot: W2W2SWNW Sec/Twnshp/Rge: 24-25S-19E  
3300 feet from S Section Line, 5040 feet from E Section Line  
Lease Name: WOLFE Well #: 45  
County: ALLEN Total Vertical Depth: 886 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	6.25	20		
PROD	2.875	886		

Well Type: EOR UIC Docket No: E10334.91 Date/Time to Plug: 01/19/2012 12:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Rcvd. from: REX R. ASHLOCK Company: Phone: (620) 365-3111

Proposed Plugging Method: RIH W/1" TGB TO BTM, FILL CSG W/CMT, POOH, "TOP OFF" W/CMT, THEN PRESSURE SQUEEZE CMT, SHUT WELL IN, RETURN AT A LATER DATE, CUT OFF CSG BELOW PLOW DEPTH.

Plugging Proposal Received By: RYAN DULING WitnessType: NONE  
Date/Time Plugging Completed 01/19/2012 8:00 AM KCC Agent: RYAN DULING

**Actual Plugging Report:**

Ran 1" pipe down the inside of the 2 7/8" casing to TD. Pumped and circulated cement through the 1" pipe inside the 2 7/8" casing from TD to surface. Pulled the 1" pipe. Topped well off with cement. Hooked onto the casing and squeezed with cement and shut well in under pressure. A total of 35 sacks of portland cement was reported used to plug this well.

**Perfs:**

Top	Bot	Thru	Comments
858	868		

RECEIVED

FEB 15 2012 RMD

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed

*[Signature]*

(TECHNICIAN) RECEIVED

*cc to MIC 2/17/12*

FEB 17 2012 Form CP-2/3

KCC WICHITA

*2/20/12*