

TO: STATE CORPORATION COMMISSIO  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 6720

API Well Number: 15-001-22150-00-00  
Spot: N2NENW Sec/Twnshp/Rge: 24-25S-19E  
4620 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: WOLFE Well #: RW-36  
County: ALLEN Total Vertical Depth: 886 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	6.25	50		50 SX
PROD	2.875	889		130 SX

Well Type: EOR UIC Docket No: E10334.86 Date/Time to Plug: 01/23/2012 12:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Rcvd. from: REX R. ASHLOCK Company: Phone: (620) 365-3111

Proposed Plugging Method: RIH W/1" TO BTM, FILL CSG W/CMT, POOH, "TOP OFF" CSG W/CMT, THEN PRESSURE SQUEEZE CMT, SHUT WELL IN, RETURN AT A LATER DATE, CUTOFF CSG BELOW PLOW DEPTH.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed 01/23/2012 1:00 PM KCC Agent: RYAN DULING

**Actual Plugging Report:**

Ran 1" pipe down inside the 2 7/8" casing to TD. Pumped and circulated cement through the 1" pipe inside the 2 7/8" casing from TD to surface. Pulled 1" pipe up to 450' and circulated cement through the 1" pipe from 450' to surface. Pulled the rest of the 1" pipe and topped well off with cement. Hooked onto casing and squeezed with cement and shut well in with #400 of pressure. A total of 35 sacks of portland cement was reported used to plug this well.

**Perfs:**

Top	Bot	Thru	Comments
850	858		
840	842		

RECEIVED  
FEB 15 2012 RMD  
KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed

[Signature]  
(TECHNICIAN)

cc to UIC 2/17/12

RECEIVED Form CP-2/3  
FEB 17 2012 2/20/12  
KCC WICHITA