

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-171-20826-00-00  
Spot: W2SESWNW Sec/Twnshp/Rge: 34-17S-34W  
3011 feet from S Section Line, 905 feet from W Section Line  
Lease Name: DOLLY Well #: 1  
County: SCOTT Total Vertical Depth: 5310 feet

Operator License No.: 5822  
Op Name: VAL ENERGY, INC.  
Address: 200 W DOUGLAS AVE STE 520  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5066		WITH 2 SX CMT
SURF	8.625	266		WITH 190 SX CMT
PROD	5.5	5309	900	WITH 100 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/23/2012 1:00 PM  
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.  
Proposal Rcvd. from: HAL HOSS Company: VAL ENERGY, INC. Phone: (316) 263-6688

Proposed Plugging Method: RUN CIBP 50' FROM PERFS. PULL CASING & SPOT 50 SX CMT AT 2400'. 80 SX CMT AT 1500'. 40 SX CMT AT 750'. 50 SX CMT AT 300'. 15 SX CMT AT 40'.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/24/2012 1:45 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 5066' WITH 2 SX CMT. COULD NOT GET CASING RECOVERY BELOW 900'. PERFORATED AT 2400' & PUMPED 50 SX CMT. 1/24/12: PERFORATED AT 1500' & PUMPED 80 SX CMT. SHOT CASING OFF AT 900' & PULLED TO 750'. PUMPED 40 SX CMT. PULLED CASING TO 300' & PUMPED 50 SX CMT. PULLED CASING & TOPPED OFF WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5158	5164		
5143	5153		
5116	5124		

Remarks: USED 60/40 4% GEL BY CONSOLIDATED & ALLIED.

Plugged through: CSG

District: 01

Signed

*Michael Maier*  
(TECHNICIAN)

RECEIVED

FEB - 3 2012

KCC DODGE CITY

RECEIVED

FEB 13 2012

KCC WICHITA

Form CP-2/3

*2/21/12*