

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-20399-00-00
Spot: SENWNENE Sec/Twnshp/Rge: 25-30S-42W
4725 feet from S Section Line, 765 feet from E Section Line
Lease Name: BAUGHMAN Well #: 1-25
County: STANTON Total Vertical Depth: 5638 feet

Operator License No.: 32628
Op Name: QUANTUM OPERATING COMPANY
Address: PO BOX 3029
DENVER, CO 80201

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1505		WITH 725 SX CMT
PROD	4.5	5637	0	WITH 565 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 01/18/2012 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT WitnessType: NONE
Date/Time Plugging Completed: 01/19/2012 5:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

1/18/12: 1ST PLUG SAND TO 5042' & 4 SX CMT. 2ND PLUG COULD NOT GET SLIPS OUT OF BRADEN HEAD. RAN BOND LOG & FOUND CMT FROM 1910' TO 82'. RIHWT TO 1600' & PUMPED 2 SX HULLS, 7 SX GEL, & 110 SX CMT. 3RD PLUG PTOH TOP OFF CASING WITH 50 SX CMT. 1/19/12: 4TH PLUG CMT FELL TO 512'. PTT TO 512 & CIRCULATED 40 SX CMT TO SURFACE. 5TH PLUG PULL TBG & TOP OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5521	5526		
5133	5149		

Remarks: USED 60/40 POZMIX 4% GEL BY QULAITY.

Plugged through: TBG

District: 01

Signed _____

Steve Durrant

(TECHNICIAN)

RECEIVED

FEB - 8 2012

KCC DODGE CITY

RECEIVED CP-2/3

FEB 13 2012 2/24/12

KCC WICHITA