

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24301-00-01
Spot: NENWNW Sec/Twnshp/Rge: 16-17S-22W
490 feet from N Section Line, 1181 feet from W Section Line
Lease Name: MNM PARTNERSHIP Well #: A1 OWWO
County: NESS Total Vertical Depth: 4535 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 912 N LOGAN PO BOX 195
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	316		WITH 200 SX CMT
T1	2.375	4438		
PC		1658		WITH 180 SX CMT
PROD	4.5	4527		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/30/2012 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: RUN TBG TO 1680' & CIRCULATE CMT. CHECK BACKSIDE WITH 50 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/30/2012 3:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SANDED BOTTOM TO 4236' WITH 4 SX CMT. RUN TBG TO 1683' & PUMPED 105 SX CMT. CMT CIRCULATED. PULLED TBG & TOPPED OFF WITH 20 SX CMT. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4336	4354		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
FEB - 9 2012
KCC DODGE CITY

RECEIVED
FEB 13 2012
KCC WICHITA