

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-179-21138-00-00  
Spot: NESWSWNE Sec/Twnshp/Rge: 13-9S-26W  
2090 feet from N Section Line, 2000 feet from E Section Line  
Lease Name: BORGER A Well #: 1-13  
County: SHERIDAN Total Vertical Depth: 4161 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	283		200 SX
T1	2.375	4110		
PC		2303		
PROD	5.5	4156		140 SX
PROD	5.5	4158		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/31/2012 10:30 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 400sx 60/40 pozmix 4% gel cement, 300# hulls, 17 sx gel.  
Stage collar @2303' w/200sx cmt

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/31/2012 1:45 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforated @1500', 790', 600'.  
Ran tubing to 3918' and pumped 17sx gel followed by 75sx cmt w/300# hulls.  
Pulled tubing to 2277' and pumped 30sx cmt.  
Pulled tubing to 1370' and pumped 150sx cmt. Cement circulated.  
PTOH. Topped off w/15sx cmt. Max Press.-350psi

Perfs:

Top	Bot	Thru	Comments
4043	4048		
4028	4032		
4020	4023		
3928	3930		

Remarks: CONSOLIDATED SERVICES #33830

Plugged through: TBG

District: 04

RECEIVED

Signed Darrel Dipman

(TECHNICIAN)

CM

FEB 14 2012

FEB 08 2012

KCC WICHITA

Form CP-2/3

2/20/12