

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05239-00-01
Spot: NENESW Sec/Twnshp/Rge: 3-11S-18W
2259 feet from S Section Line, 3044 feet from E Section Line
Lease Name: MEISTRELL Well #: B-2 SWD
County: ELLIS Total Vertical Depth: 956 feet

Operator License No.: 30553
Op Name: UNREIN, GLENN DBA UNREIN OIL CO
Address: 300 W 40TH ST
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	158		150 SX
L1	3.5	956		
PROD	5.5	3590		75 SX

Well Type: SWD UIC Docket No: D19449.0 Date/Time to Plug: 02/10/2012 12:00 PM
Plug Co. License No.: 33771 Plug Co. Name: ULTIMATE WELL SERVICE, LLC
Proposal Rcvd. from: STEVEN THOMASON Company: UNREIN OIL CO. Phone: (785) 623-1174

Proposed Plugging Method: Ordered-180 sxs 60/40 poz mix. 400 # hulls

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/12/2012 3:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Ultimate Well Service RIH with tubing to 860' Allied rigged to tubing & pumped 135 sxs with 150 # hulls mixed in, lost circulation.
Pulled tubing rigged to 3.5" CSG & pumped 10 sxs with 50 # hulls mixed in to pressure with 500 # PSI & 300 # SIP.
Rigged to 8.625" CSG & pumped 35 sxs to pressure with 200 # PSI & 100# SIP.

Perfs:


Top	Bot	Thru	Comments
860	890		CEDAR HILLS

Remarks: ALLIED CEMENTING CO. TICKET 34565

Plugged through: TBG

District: 04

Signed



RECEIVED

(TECHNICIAN)

CM

FEB 13 2012

FEB 14 2012

KCC WICHITA

cc to WC 2/14/12 2/21/12