

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22948-00-00
Spot: NESWSW Sec/Twnshp/Rge: 6-11S-18W
990 feet from S Section Line, 4290 feet from E Section Line
Lease Name: PEAVEY Well #: 2
County: ELLIS Total Vertical Depth: 3730 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3252		was knocked down to 3421'
SURF	8.625	295		165 SX
PROD	5.5	3730		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/06/2012 1:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTRE Company: QUALITY WELL SERVICE Phone: (620) 727-3409

Proposed Plugging Method: Ordered-475 sxs 60/40 poz mix 4 % gel: 500 # hulls
Perf Tech perfed @ 2020; 1408; 780; 285
CIBP @ 3252 was knocked down to 3421
Operator had acidized well with 30,500G 28% HCL & 4300# Benzoic AC Flakes.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/06/2012 5:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Quality Well Service RIH with tubing to 3296', Quality rigged to tubing with a swedge & mixed & pumped 100 sxs 60/40 poz with 125 # hulls mixed in.
Pulled tubing to 2300' Quality rigged to tubing & mixed & pumped 100 sxs pox mix with 150# hulls mixed in.
Pulled tubing to 1300' Quality rigged to tubing & mixed & pumped 173 sxs poz mix with 150 # hulls mixed into circulate cement to surface.
Pulled tubing topped off 5-1/2" CSG with 25 sxs cement to fill CSG. Hole was standing full.
Rigged to 8-5/8" CSG with a swedge & valve & pumped 15 sxs to pressure with 300 # PSI & 200 # SIP.

Perfs:


Top	Bot	Thru	Comments
3549			

Remarks: QUALITY WELL SERVICE (31925) TICKET # 5350

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)
RECEIVED

CM

FEB 07 2012

FEB 14 2012

Form CP-2/3

KCC WICHITA

2/21/12