

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-23922-00-00  
Spot: SWSESW Sec/Twnshp/Rge: 26-19S-15W  
382 feet from S Section Line, 3750 feet from E Section Line  
Lease Name: SCHARTZ Well #: 3  
County: BARTON Total Vertical Depth: 3736 feet

Operator License No.: 30742

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	870	400	SX
PROD	5.5	3642	150	SX

Op Name: PALOMINO PETROLEUM, INC.

Address: 4924 SE 84TH ST  
NEWTON, KS 67114

Well Type: SWD

UIC Docket No: D23977.0

Date/Time to Plug: 01/30/2012 9:00 AM

Plug Co. License No.: 6901

Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Rcvd. from: RICK SCHREIBER

Company: PALOMINO

Phone: (316) 799-1000

Proposed Plugging Method: Ordered 350sx 60/40 pozmix 4% gel, 300# hulls.

Plugging Method:

Plugging Proposal Received By: BRUCE BASYE

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 01/30/2012 1:00 PM

KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Sanded off perfs. Dump bailed 5sx cmt.  
Cut casing off @1728'. Pulled to 1650'. Pumped 180sx cmt w300# hulls.  
Pulled casing to 870'. Pumped 50sx cmt.  
Pulled casing to 400'. Circulated w/90sx.

Remarks: COPELAND ACID AND CEMENT

Plugged through: CSG

District: 04

Signed Bruce Rodie (TECHNICIAN)

CM

RECEIVED

FEB 14 2012

KCC WICHITA

FEB 08 2012

Rec'd NC 2/14/12 Form CP-2/3  
2/20/12