

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-23851-00-00
Spot: SENWSWSW Sec/Twnshp/Rge: 26-19S-15W
660 feet from S Section Line, 330 feet from W Section Line
Lease Name: SCHARTZ Well #: 1
County: BARTON Total Vertical Depth: 3569 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH ST
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	884		
PROD	5.5	3569		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/31/2012 12:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: RICK SCHREIBER Company: PALOMINO Phone: (316) 799-1000

Proposed Plugging Method: Ordered 350sx 60/40 pozmix 4% gel cement. 300# hulls

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/31/2012 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Sanded off perfs and dump bailed 5sx cmt. Bailer stuck in hole. Cut line and left.
Cut casing @1700'. Pulled casing to 1650' and pumped 180sx cmt w/300# hulls.
Pulled casing to 400' and circulated w/100sx cmt.
Pulled rest of casing. Topped off w/12sx cmt.

Remarks: COPELAND ACID AND CEMENT

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

RECEIVED

FEB 14 2012

KCC WICHITA

Form CP-2/3

FEB 08 2012

✓ 2/21/12