

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-22511-00-00  
Spot: SWNWNENE Sec/Twnshp/Rge: 34-21S-19E  
4930 feet from S Section Line, 1016 feet from E Section Line  
Lease Name: KELLSTADT Well #: 3184  
County: ANDERSON Total Vertical Depth: 850 feet

Operator License No.: 33097  
Op Name: SOUTHERN STAR CENTRAL GAS PIPE  
Address: 4700 HWY 56  
OWENSBORO, KY 42301

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF   | 6.625 | 21         |             |          |
| PROD   | 2.875 | 830        |             |          |

Well Type: EOR UIC Docket No: E11406.16 Date/Time to Plug: 01/04/2012 12:00 PM  
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.  
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Run work string to bottom, cement to surface. Pull work string out, tie onto well, and squeeze cement until desired pressure is achieved. Cut pipe off 3' below surface, cap, and backfill.

Plugging Proposal Received By: JOHN ALMOND Witness Type: NONE  
Date/Time Plugging Completed: 01/04/2012 11:00 AM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran 1' pipe to TD, circulated portland cement to surface, pulled 1" out, hooked on to 2-1/2" casing and squeezed cement into well, shut in at 500 psi. Contractor indicated that they used 45 sacks cement to plug well.

Perfs:

| Top | Bot | Thru | Comments |
|-----|-----|------|----------|
| 830 | 850 |      | SQUIRREL |

RECEIVED

FEB 13 2012 JA

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed

*John Almond*  
(TECHNICIAN)

cc to UIC 2/17/12

RECEIVED Form CP-2/3  
FEB 16 2012 2/21/12  
KCC WICHITA