

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-22512-00-00  
Spot: E2NESWSE Sec/Twnshp/Rge: 34-21S-19E  
990 feet from S Section Line, 1392 feet from E Section Line  
Lease Name: KELLSTADT Well #: 4 I 84  
County: ANDERSON Total Vertical Depth: 854 feet

Operator License No.: 33097  
Op Name: SOUTHERN STAR CENTRAL GAS PIPE  
Address: 4700 HWY 56  
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	6.25	21		5 SX
PROD	2.875	834		98 SX

Well Type: EOR UIC Docket No: E11406.19 Date/Time to Plug: 01/04/2012 12:00 PM  
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.  
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: RUN WORK STRING TO BOTTOM, CEMENT TO SURFACE. PULL WORK STRING OUT AND TOP OFF WELL W/ CEMENT. TIE ONTO WELL AND SQUEEZE CEMENT UNTIL DESIRED PRESSURE IS ACHIEVED. CUT OFF WELL 3' BELOW SURFACE.

Plugging Proposal Received By: JOHN ALMOND Witness Type: NONE  
Date/Time Plugging Completed: 01/04/2012 3:00 PM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran 1" to TD, circulated portland cement to surface, pulled 1" pipe out, hooked on to 2-1/2" casing and squeezed cement into well, shut in at 750 psi. Contractor indicated that they used 45 sacks cement to plug well.

Perfs:

Top	Bot	Thru	Comments
834	854		SQUIRREL

RECEIVED

FEB 13 2012 JA

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed

  
(TECHNICIAN)

cc to MC 2/17/12

RECEIVED Form CP-2/3

FEB 16 2012 2/21/12

KCC WICHITA