


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Saline County. Sec. 25 Twp. 15 Rge. 3 (E) (W)
Location as "NE/CNW%SW%" or footage from lines CNW NW
Lease Owner Morrison Producing Company
Lease Name Pinkler Well No. 1
Office Address El Dorado, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 4/21/67 19
Plugging completed 4/22/67 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes
Name of Conservation Agent who supervised plugging of this well Toman

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3245 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	248	none
				5 1/2	3236	2628

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked bottom, ran sand to 3200', dumped 5 sacks of cement. Loaded hole, shot pipe at 2619', pipe came loose. Set 10' rock bridge at 245' to 235', dumped 20 sacks of cement, mudded to 40' rock bridge to 30', dumped 10 sacks of cement. Talled pipe.

PLUGGING COMPLETE.

APR 26 1967
04-26-1967

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) *Noel Knight*
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN to before me this 24th day of April, 1967
Margaret Melcher
Notary Public.
My commission expires February 15, 1971

MORRISON PRODUCING COMPANY

H. J. Tinkler - Well #1

15-169-00475-00-00
C NW/4 NW/4

Total Depth - 3250'

Contractor - Graves Drig. Co., Inc. Section 29-15S-3W

Commenced 10-2-61

Saline County, Kansas

Completed - 10-8-61

5/8" set @ 254 ft.

<u>FORMATION</u>	<u>DEPTH</u>
Sand	42
Shale	134
Lime	286
Shale	298
Lime	360
Shale	406
Shale & lime stras	475
Sand	592
Shale	1330
Lime	1461
Shale & lime stras	1623
Lime - sandy	1683
Shale	1866
Lime	1930
Sandy shale	2015
Shale	2260
Lime	2415
Lime - shale stras	2606
Shale	2774
Lime	2997
Shale	3240
Lime	3250 T.O.

APR 21 1967
04-21-1967
CONSERVATION DIVISION
WICHITA, KANSAS

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

STATE OF KANSAS)
COUNTY OF BUTLER) SS

By *John C. Graves*

Subscribed and sworn to before me, a Notary Public, this 12th day of October, 1961.

Maxine Jarchick
(Notary Public)

My commission expires:
Nov. 23, 1963