


STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

15-169-00210-00-00

NORTH



Locate well correctly on above
Section Plat

Saline

County, Sec. 25 Twp. 15 Rge. 3 (E) W (W)

Location as "NE/CNW&SW&" or footage from lines W 35 acres SW/4

Lease Owner Mutual Oil Company

Lease Name Collins

Well No. 1

Office Address Denver, Colorado

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed

19

Application for plugging filed

19

Application for plugging approved

19

Plugging commenced 2-1-62

19

Plugging completed 2-3-62

19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production

19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Cecil Jones

Producing formation Depth to top Bottom Total Depth of Well 3295 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	260'	None
				4-1/2"	3294'	2606'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3295', ran and dumped 5 sacks of cement with dump bailer. Pulled 4 1/2" casing checked fluid to 240', set rock bridge to 230' and ran 20 sacks of cement. Mudded to 35', set rock bridge to 25' and ran 8 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING COMPLETE.

MAR 3 1962
03-06-7962
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE
Noel J. Knight, ss.

(employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Noel J. Knight

Chase, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 6th day of February, 1962

My commission expires May 20, 1964

Notary Public.



15-169-00210-00-00

The Mutual Oil Co., Inc., Lease Owner

Donald T. Ingling, Contractor

Commenced: 5-27-61

Completed: 6-6-61

Total Depth: 3295 (rotary)

Casing: 8 5/8" 260' (175 sacks cement)
4 1/2" 3290 1/2' (60 sacks cement)

Section 25-15-3W

C W/2 NW SW, Location

County: Saline

Production:

Elevation: 1275 RB

Figures below indicate bottom formation

45 surface clay
 80 sand
 215 shale and shells
 260 lime
 540 lime and shale streaks
 745 lime
 955 lime and shale streaks
 1240 shale and lime shells
 1500 shale and shells
 1690 lime
 1825 lime
 1900 lime
 1960 shale and lime
 2150 lime
 2255 lime
 2355 lime
 2470 lime
 2560 lime
 2710 shale and lime
 2725 Mississippi
 2920 Mississippi
 2975 Mississippi
 3023 Mississippi
 3030 lime
 3090 shale and lime
 3190 shale
 3198 shale
 3217 lime - Hunton
 3270 shale
 3290, shale
 3295 dolomite
 3295 Total Depth

RECEIVED
 STATE CORPORATION COMMISSION

MAR 6 1962
 03-06-1962
 CONSERVATION DIVISION
 Wichita, Kansas

I certify this is a true and correct copy of the above mentioned well.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss

Subscribed and sworn to before me, a Notary Public, in said county and state.

My commission expires: Feb. 27, 1964