


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Saline County. Sec. 17 Twp. 15 Rge. 3 (E) W
Location as "NE/CNW&SW4" or footage from lines C of NL SE SW
Lease Owner Salina Basin Pet. Co.
Lease Name Percival Well No. 1
Office Address 110 So. Santa Fe. Salina, Kans.
Character of Well (completed as Oil, Gas or Dry Hole) Oil in testing stage
Date well completed May 22 1963
Application for plugging filed May 22 1963
Application for plugging approved May 22 1963
Plugging commenced May 22 1963
Plugging completed May 22 1963
Reason for abandonment of well or producing formation Dry hole
Abandoned because of completion difficulty

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well G. Tomar
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3381 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Steel Plug set at 3355 to shut of Viola. Dumped rock & 3 sks Cement to 3335 to shut Maquoketa
Bridged from 325' to 300' Rock Bridge
Cemented to surface with 3 yds. ready mix cement

RECEIVED
STATE CORPORATION COMMISSION
JUN 3 1963
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Triangle Drilling Co.
Address 324 N. Orchard, El Dorado, Kans.

STATE OF Kansas, COUNTY OF Butler, ss.
Harry Hughes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harry Hughes

SUBSCRIBED AND SWORN TO before me this 27 day of May 1963
My commission expires October 6, 1963
John L. Bove Notary Public.

R 15-169-00224-00-01

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Saline Basin Petroleum Company
119 South Santa Fe
FARM Percival No. 1.

SEC. 17 T. 15 R. 3 W
LOC. C of NL SE SW

TOTAL DEPTH 3381

COMM. 9/2/62

COMP. 9/9/62


SHOT OR TREATED Acid and Frack Plugged: 5/22/63

CONTRACTOR White and Ellis

ISSUED

COUNTY Saline

KANSAS



CASING 8 5/8 329 ft.
Cemented 250 sks.

20
15
12
13

10
8
6
5

ELEVATION 1285 GL

PRODUCTION Dry

FIGURES INDICATE BOTTOM OF FORMATIONS

0 to 130	Sod and Shale
275	Shale and Lime
258	" "
700	Shale and Lime
1860	Lime
2095	Shale and Lime
2300	Lime
2510	Lime and Shale
2670	Shale
2810	Lime (Miss.)
3190	Shale
3284	Lime, Hunton
3290	Shale
3381	Dolemite

Geologists Tops

Miss.	2797
Miss. Dol	2810
Misner Sand	3244
Hunton	3252
Maquoketa Shale	3284
Maquoketa Dol	3350
T D	3381

RECEIVED
STATE CORPORATION COMMISSION

JUN 3 1963

06-03-1963

CONSERVATION DIVISION
Wichita, Kansas