

15-169-00004-0000


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Salina County, Sec. 16 Twp. 15S Rge. 3 (E) (W)

Location as "NE/CNW&SW" or footage from lines SW SW SE
Lease Owner National Cooperative Refinery Association
Lease Name Schultz Well No. 1
Office Address 305 Rule Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 6, 1956
Application for plugging filed September 18, 1956
Application for plugging approved September 12, 1956
Plugging commenced September 6, 1956
Plugging completed September 6, 1956
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3550 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	350'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Mudded hole to 180'. Set plug with 20 sacks of cement. Mudded hole to 40'.
Set plug with 10 sacks of cement on up to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mallard Drilling Company
Address 1016 Union National Building, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.
C. R. Sears (employee of owner) or (partner of plaintiff) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. Sears (C. R. Sears)
305 Rule Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of September, 1956

My commission expires November 26, 1956.

Nell McComb Notary Public.

PLUGGING
FILE SEC 16 T 15 R 3W
BOOK PAGE 100 LI 16

09-19-1956

15-169-00004-00-00

COMPANY: N.C.R.A., et al
 CONTRACTOR: Mallard Drilling Company
 FARM: Schultz #1
 LOCATION: SW SW SW Sec. 16-158-3W
 Saline County, Kansas
 COMMENCED: August 25, 1956
 COMPLETED: September 5, 1956

0	to	20	Shale
20	to	60	Sand
60	to	285	Shale and shells
285	to	351	Anhydrite
351	to	675	Lime and shale
675	to	835	Lime
835	to	1720	Shale and lime
1720	to	2133	Shale and lime
2133	to	2255	Kansas City
2255	to	2610	Lime and shale
2610	to	2745	Shale and lime
2745	to	2845	Lime and chert
2845	to	2990	Mississippi
2990	to	3030	Lime
3030	to	3200	Shale
3200	to	3208	Miss. Sand
3208	to	3215	Hunter
3215	to	3270	Lime and shale
3270	to	3298	Shale
3298	to	3345	Dolomite and shale
3345	to	3355	Shale
3355	to	3382	Viola lime
3382	to	3494	Lime
3494	to	3520	Sand
3520	to	3550	Arbuckle
3550	to		T.D. Rotary

Set 351 feet of 8 5/8" surface pipe. Cemented with 225 sacks cement, 2 cal. chloride.

TOPS: Toronto Line--1940 Douglas Sand--1990 Kansas City --2133
 Chat --2750 Misener--3197 Hunter Line-- 3209
 Maquoketa shale--3229 Maquoketa Dolomite --3299
 Viola Line--3320 Simpson--3487
 Arbuckle--3522

Measurements taken from R.D.B. R.D.B. 5 1/2' from ground level
 Run D.S.T. 3363 to 3383 Run D.S.T. 3484 to 3494
 DRY, ABANDONED AND PLUGGED

C E R T I F I C A T E

I, C. C. Nelson, do hereby certify that the above and foregoing is a true and correct copy of log of the Schultz #1, Saline County, Kansas, as reflected by files of the Mallard Drilling Company.

C. C. Nelson

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County Kansas, this 7th day of September 1956.

Robert A. Hurd

My commission expires 11-16-56

PLUGGING
 FILE SEC. 16 T. 15 R. 3W
 BOOK PAGE 100 LINE 23
 48 16

09-19-1954