

15-169-20087-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Saline County, Sec. 8 Twp. 15 Rge. 3W (E) (W)

Location as "NE/CNWxSWx" or footage from lines SW SE NE

Lease Owner Brandt Oil Company

Lease Name J. W. Carlin Well No. 1

Office Address 1103 Douglas Bldg, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed August 23, 1978

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 19

Plugging completed August 23, 1978

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Shale & Shells		0	300'	8 5/8"	300'	None
Anhydrite		300'	359'	8 5/8"	59'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set bottom plug at 250' with 25 sacks of cement. Filled with mud to 40' with 10 sacks of cement, 2 sacks in rathole. Job completed at 6:00 A. M., August 23, 1978. Plugging completed by State Plugger, Gilbert Toman, Holyrood, Kansas.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 31 1978  
08-31-1978  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Blackstone Drilling, Inc.

Address Box 1184, McPherson, Kansas 67460

STATE OF Kansas, COUNTY OF Sedgwick ss.

Brandt Oil Company (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. BRANDT OIL COMPANY


(Signature) BY: Earl O Brandt

1103 Douglas Bldg, Wichita, Kansas 67202 (Address)

Subscribed and sworn to before me this 30th day of August, 1978

Barbara June Brandt  
Barbara June Brandt Notary Public.

My commission expires February 29, 1980





15-169-20087-00-00

# Blackstone Drilling, Inc.

Box 1184, 523 West Kansas • Phone (316) 241-1250  
McPHERSON, KANSAS 67460

August 23, 1978

COMPANY: BRANDT OIL COMPANY  
 CONTRACTOR: BLACKSTONE DRILLING, INC.  
 FARM: J. W. CARLIN #1  
 LOCATION: SW/4 SE/4 NE/4 Section 8-15-3W,  
 Saline County, Kansas  
 COMMENCED: August 16, 1978  
 COMPLETED: August 23, 1978  
 ELEVATION:

0	to	300	Shale & Shells
300	to	364	Anhydrite
364	to	935	Lime & Shale
935	to	1880	Shale & Lime
1880	to	2260	Lime
2260	to	2472	Lime & Shale
2472	to	2630	Lime
2630	to	2789	Shale & Lime
2739	to	2790	Mississippi
2790	to	2908	Lime & Shale
2908	to	3095	Lime
3095	to	3325	Lime & Shale
3325	to	3406	Shale & Lime
3406	to	3470	Lime & Shale
		3470	T. D.

08-31-1978

Cut 12 1/2" hole to 359' and run 361' of 8 5/8" surface pipe, cemented with 200 sacks of 2X Gel & 3X CC at 259'. Plug down at 12:00 Noon, August 16, 1978. Cut 7 7/8" hole to 3470'. Hole dry and abandoned. Set bottom plug at 250' with 25 sacks of cement. Filled with mud to 40' with 10 sacks of cement, 2 sacks in rat-hole. Plugging completed at 6:00 A. M., August 23, 1978. Plugging completed by Gilbert Toman, Holyrood, Kansas, State Plugger.

TOPS:

Measurements taken from K. B.

### CERTIFICATE

I, F. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your J. W. Carlin #1, located on the SW/4 SE/4 NE/4 Section 8-15-3W, Saline County, Kansas as reflected by the files of Blackstone Drilling, Inc.

  
 F. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 24th day of August, 1978.

  
 Johnnie L. Schmidt - Notary Public

