


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Saline County. Sec. 29 Twp 14 Rge. 2 (E) W (W)
Location as "NE/CNWxSWx" or footage from lines. NW NW NW
Lease Owner West Supply Co., Inc.
Lease Name Morrison #1 Well No. _____
Office Address Chase, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed 5- 5-58 19____
Application for plugging approved 5- 7-58 19____
Plugging commenced 5-19-58 19____
Plugging completed 5-23-58 19____
Reason for abandonment of well or producing formation
Depletion

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3243 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	187'	none
				7"	3235'	2680 1/2'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked the hole to 3243' and found it open.
Filled w/sand to 3223' and ran 6 sacks of
cement with dump bailer. Pulled 7" casing.
Cleared hole, bailed oil and mudded hole to
180', set a 10' rock bridge and ran 25 sacks
of cement. Mudded hole to 30', set rock
bridge and ran 10 sacks of cement to base
of cellar.

Sum
MAY 29 1958
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.

_____(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of May, 1958

Thomas V. Duggin
Notary Public.

My commission expires 4-27-59

PLUGGING
FILE SEC 29 T. 14 R2W
BOOK PAGE 99 LINE 3

COMPANY: Westgate-Greenland Oil Company
 CONTRACTOR: C. C. Nelson Drilling Company
 FARM: ZE11A Morrison #1
 LOCATION: NW NW NW,
 Section 29-14-2W
 Saline County
 COMMENCED: August 12, 1944
 COMPLETED: September 19, 1944
 ELEVATION: 1258 Feet

0	to	80	Shale
80	to	180	Shale and shells
180	to	310	Lime
310	to	330	Sandy lime
330	to	490	Lime and shale
490	to	635	Sandy lime
635	to	875	Shale and lime
875	to	1110	Shale
1110	to	1280	Shale and shells
1280	to	1420	Lime
1420	to	1600	Shale
1600	to	1885	Lime
1885	to	2050	Shale
2050	to	2605	Lime
2605	to	2647	Shale
2647	to	2665	Lime and sand
2665	to	2685	Lime
2685	to	2700	Chat
2700	to	2730	Lime and chert
2730	to	2820	Chat
2820	to	2890	Lime and chert
2890	to	2893	Shale
2893	to	2900	Chert and lime
2900	to	2995	Lime
2995	to	3085	Shale
3085	to	3170	Lime
3170	to	3235	Shale
3235	to	3240	Viola lime - oil show
3240	to	3243	Chert - water show
		3243	T. D.

Set 187 feet of 10 3/4 inch surface pipe. Cemented with 110 sacks cement.
 Set 3235 feet of 7 O. D. 20# pipe. Cemented with 75 sacks cement.

700' of oil in hole in 6 hrs.
 1700' of fluid in hole in 26 hrs.
 250' of water in hole in 26 hrs.

3237' T. D. of rotary
 3243' T. D. Cable tools
 249 Bbls. State Potential
 Measurements from top of derrick floor

CERTIFICATE

I, Clare A. Stewart, do hereby certify that the above and foregoing is a true and correct copy of log of the Morrison #1, Section 29-14-2W, Saline County Kansas, as reflected by files of the C. C. Nelson Drilling Company.

PLUGGING
FILE SEC. 29-14-2W
BOOK PAGE 99 LINE 3

MAY 27 1944