

15-169-00428-00-00


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
911 No. Broadway  
Wichita, Kansas

Salina County, Sec. 29 Twp. 14 Rge. 2 (X) (W)

Location as "NE/CNWxSWx" or footage from lines SE SE NW  
Lease Owner Rochwile, Inc.  
Lease Name Becker Unit Well No. 1  
Office Address 503 Mayo Bldg., Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 12-17-62 19  
Application for plugging filed 10-15-63 19  
Application for plugging approved 10-21-63 19  
Plugging commenced 10-21-63 19  
Plugging completed 10-26-63 19  
Reason for abandonment of well or producing formation Not Commercial

NORTH



Locate well correctly on above  
Section Plot

If a producing well is abandoned, date of last production 9-11-63 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well GILBERT TOMAN Gilbert Toman  
Producing formation Dolomite Depth to top 3268 Bottom 3276 Total Depth of Well 3315 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Dolomite	Oil	3268	3276	8 5/8 4 1/2	248' 3313'	None 2798'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled back above perforations with sand and dumped (3) sacks of cement. Shot off pipe at 2798'. Pulled pipe and mudded hole to 240'. Set rock bridge and finished filling hole with ready mix cement.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 13 1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bert Self  
Address Hutchinson, Kansas

STATE OF Oklahoma, COUNTY OF Creek, ss.  
George J. Turner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. J. Turner  
G. J. TURNER  
P.O. BOX 717, SAPIILPA, OKLAHOMA  
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of November, 19 63

My commission expires 6/27/64

Walter  
Notary Public.

15-169-00428-00-00

**LOG**

DESCRIPTION SE/4 SE/4 Sec. 29-14S-2W

State Kansas Company Rochwile, Inc.

County Saline Farm Becker Unit Well No. 1

Survey

T. R. Contractor White & Ellis Drlg.

Commenced 11-26-62

Completed 12-6-62

Remarks

Elev. DF. 1296'

Altitude GF. 1294'

Production

**CASING RECORD**

10 "

~~18~~ 5/8" 248'

20 " 6 3/4"

15 1/2" 5 3/4"

12 1/2" 4 1/2" 3313'

Shot Quarts Between

**Log-Continued**

Top Bottom Formation and Remarks

8 5/8" 248' C/W 200 Sacks

4 1/2" 3313' C/W 125 Sacks

Perforated - 3268' to 3276'

8 Holes per foot total of

64 holes

Frac. W/30,000# Sand,

2,200 bbls. water

Top	Bottom	Formation and Remarks
0	50	Clay
50	125	Shale
125	175	Shale & Lime Stks.
175	244	Lime & Shale
244	248	Lime
248	400	Lime & Shale
400	640	Shale & Lime
640	950	Lime
950	1310	Shale & Lime
1310	1370	Lim & Shale
1370	1450	Shale
1450	1600	Shale & Lime
1600	1940	Lime & Shale
1940	2065	Shale
2065	2525	Shale & Lime
2525	2710	Shale & Lime
2710	2719	Shale
2719	2962	Lime
2962	3088	Shale
3088	3174	Lime
3174	3270	Shale
3270	3315	Lime
<del>3315</del>	3315	T. D.

188 FOR MARTIN CO. TULSA, OKLAHOMA

RECEIVED  
STATE CORPORATION COMMISSION

NOV 18 1963

CONSERVATION DIVISION  
Wichita, Kansas

