

15-071-20019-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

Greeley County, Sec. 11 Twp. 19S Rge. 40W (EX) (W)  
Location as "NE/CNW&SW" or footage from lines C NW  
Lease Owner Dorchester Exploration, Inc.  
Lease Name Miller #1 Well No. 1  
Office Address 1204 Vaughn Building, Midland, Texas 79701  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed January 14, 1973 19  
Application for plugging filed January 13, 1973 19  
Application for plugging approved January 13, 1973 19  
Plugging commenced 7:00 P.M., January 14, 1973 19  
Plugging completed 8:45 P.M., January 14, 1973 19  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 2908 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	375	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud.  
110 cubic feet of 50-50 Pozmix, 6% gel, through open end of drill pipe; filled with mud to 400', 30 cubic feet of cement through open end; filled to 40', solid bridge, Howco plug, 1/2 sack hulls, 10 cubic feet cement.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 6 1973  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor STERLING DRILLING COMPANY  
Address P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS, COUNTY OF RICE, ss.  
F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY

(Signature) [Signature]  
F. A. Wuellner, Secretary  
P. O. Box 129, Sterling, Kansas 67579  
(Address)

SUBSCRIBED AND SWORN to before me this 20th day of January, 19 73

Bernard Lauder milk  
Bernard Lauder milk, Notary Public.

My commission expires \_\_\_\_\_  
BERNARD LAUDERMILK - NOTARY PUBLIC  
My Commission Expires Jan. 22, 1974

STERLING DRILLING COMPANY  
 P. O. Box 129  
 Sterling, Kansas 67579

WELL LOG ----- MILLER #1  
 Located: C NE<sup>4</sup>, Section 11-19S-40W, Greeley County, Kansas

OWNER: Dorchester Exploration, Inc.  
 ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: January 9, 1973  
 COMPLETED: January 14, 1973

TOTAL DEPTH: 2908'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 300 Clay and Shale	Ran 8 joints 10 3/4" casing, 366' set at 375 K.B. Cemented with 150 sacks common with 2% cc, followed with 150 sacks light with 3% cc. Plug down 1:00 PM, 1-10-73.
300 - 1060 Shale	
1060 - 1790 Lime and Shale	
1790 - 1990 Shale	
1990 - 2420 Shale, Salt, Lime	
2420 - 2908 Lime and Shale	Plugged.

RECEIVED  
 STATE CORPORATION COMMISSION

FEB 20 1973

CONSERVATION DIVISION  
 Wichita, Kansas