

15-169-20014-00-00

Form CP-3
Rev. 6-9-67

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

REC 21 1967
12-21-67

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Frank J. Black

Complete Address Box 150, Mc Pherson, Kansas 67460

Lease Name Hubbard Well No. 3

Location C NE SW Sec. 23 Twp. 15 Rge. 2 (E) (W) X

County Saline Total Depth 2725'

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Co., Inc.

Address Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 1 PM Day 14 Month December Year 1967

The above well was plugged as follows:

Hole filled with sand to 2700' and cemented with 5 sacks.
Hole filled with mud to 135'. Rock bridge set from 135' to 125' and hole cemented with 25 sacks. Hole filled with mud to 40'. Rock bridge set from 40' to 30' and hole cemented to base of cellar with 10 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: William B. Lomax
Well Plugging Supervisor

12/22/67

INV. NO 6950-4