

15-169-19050-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 28 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Frank J. Black

Complete Address: Box 150 McPherson, Kansas 67460

Lease Name Hubbard Well No. # 2

Location NE SE SW Sec. 23 Twp. 15 Rge. 2 NE (W)

County Saline Total Depth 2735'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Glenn & Smith Pipe Pulling Company

Address: Ellinwood, Kansas License No. # 396

Operation Completed: Hour 5 PM Day 26 Month 7 Year 69

The Above well was plugged as follows:

10 3/4"-138'-Circulated w/cement. 7"-2732'-Cemented. Sand hole to 2730'.

6 Sax.cement 2730' to 2680'. Mud 2680' to 150'. Bridge 150' to 140'.

30 Sax.cement 140' to 80'. Mud 80' to 40'. Bridge 40' to 30'.

15 Sax.cement 30' to 0. Pulled 2286'-7"-Pipe.

I hereby certify that the above well was plugged as herein stated.

Signed: *Hugh Scott*
Well Plugging Supervisor

INDEXED

DATE 7/28/69

INV. NO. 170-W