

15-169-19056-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NE NE SE

SEC. 15 TWP. 15 RGE. 2 W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. ONE(1) Lease Ross

Operator A. H. Harper Address Burton, Kansas.

Field Baehofer County Saline

Total Depth 2835 Feet.

(Describe briefly the manner in which the well was plugged)

This well was plugged from the bottom(2835 ft.) back
up to 165 ft.with heavy rotary mud. The hole was then
bridged,and cemented with 15 sacks of cement. Then mud-
ded again to within a few feet of the top,and cemented
again with 5 sacks of cement. There was no oil string
run. There was 164 ft.of 8-5/8" surface pipe set,cemented,
that was left in the hole.

FILED
NOV 15 1951
WICHITA, KANSAS
PAGE 14 LINE 22

[Signature]
District Conservation Agent
Date November 3, 1951.

11-06-51