

15-169-19064-00-01

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

MAY 3 1967
CONSERVATION DIVISION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Donald T. Ingling

Complete Address: 615 First Nat'l Bank Bldg., Wichita, Kansas

Lease Name Altman Well No. 3

Location SW SE SW Sec. 6 Twp. 15 Rge. 2 (E) (W) X

County Saline Total Depth 3505'

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated:

Plugging Contractor: Bert Self Casing Pulling Co.

Address: R. R. #4, Hutchinson, Kansas License No. 48

Operation Completed: Hour 5 PM Day 27 Month April Year 1967

The Above well was plugged as follows:

Hole filled with sand to 3450' and cemented with 3 sacks.
(Hole bridged over at 75', and after spending 5 hours trying to knock bridge out,
decided to cement it at that point) Hole cemented to base of cellar with 6 yards
ready mix cement. (Apparently a good deal of this cement went on through the bridge,
as very little stayed in cellar. I actually think that the 145' of 20" casing is
full. as the hole was bridged off below the casing before plugging was started.)

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 5/1/67
INV. NO. 5136-W

Signed: [Signature]
Well Plugging Supervisor