

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20759-00-03
Spot: NWNWNWSE Sec/Twnshp/Rge: 19-32S-28W
2436 feet from S Section Line, 2627 feet from E Section Line
Lease Name: CLAWSON Well #: 1-19 OWWO
County: MEADE Total Vertical Depth: 5700 feet

Operator License No.: 5011
Op Name: VIKING RESOURCES, INC
Address: 400 N WOODLAWN ST, STE 18
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4850		WITH 2 SX CMT
SURF	8.625	1574		
PKR		5435		
PROD	5.5	5668	1996	WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/18/2012 11:00 AM
Plug Co. License No.: 8733 Plug Co. Name: DUNKIN, JERRY, INC.
Proposal Rcvd. from: BUTCH DUNKIN Company: DUNKIN, JERRY, INC. Phone: (580) 237-6152

Proposed Plugging Method: SET CIBP @ 4850' WITH 2 SX CMT. PLUG AT 1600' WITH 15 SX GEL & 50 SX CMT. PLUG AT 660' WITH 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: NONE
Date/Time Plugging Completed: 01/18/2012 2:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 4850' WITH 2 SX CMT. 1ST PLUG AT 1600' WITH 15 SX GEL & 70 SX CMT. 2ND PLUG AT 660' WITH 50 SX CMT. 3RD PLUG AT 330' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. CMT CIRCULATED. HOLE STAYED FULL.

Perfs:


Top	Bot	Thru	Comments
5575	5595		
5510	5515		
4898	4901		

Remarks: USED 60/40 POZMIX 4% GEL BY JERRY DUNKIN.

Plugged through: TBG

District: 01

Signed


(TECHNICIAN)

RECEIVED

JAN 24 2012

KCC DODGE CITY

RECEIVED
JAN 27 2012
KCC WICHITA

Form CP-28

1/20/12