

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-20498-00-00
Spot: SWSW Sec/Twnshp/Rge: 23-30S-18W
629 feet from S Section Line, 666 feet from W Section Line
Lease Name: UNRUH CURTIS Well #: 1
County: KIOWA Total Vertical Depth: 5089 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	519		WITH 400 SX CMT
PROD	5.5	5074	1650	WITH 260 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/19/2012 4:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2534

Proposed Plugging Method: SAND BACK TO 5000' & 5 SX CMT. PLUG AT 1200' WITH 15 SX GEL & 50 SX CMT. PLUG AT 540' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: PARTIAL
Date/Time Plugging Completed: 01/19/2012 7:00 PM KCC Agent: DANIEL BERNASCONI

Actual Plugging Report:

SANDED BACK TO 5000' WITH 5 SX CMT ON TOP. 1ST PLUG AT 1200' WITH 15 SX GEL & 50 SX CMT. DID NOT CIRCULATE BUT DID BLOW BACK. 2ND PLUG AT 540' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT. CIRCULATED TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
5074	5089		MISSISSIPPI - OH
5054	5064		UPPER MISSISSIPP

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED

JAN 23 2012

KCC DODGE CITY

RECEIVED
JAN 27 2012
KCC WICHITA

Form CP-104

1/30/12