

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-23730-00-00
Spot: NESEWNNE Sec/Twnshp/Rge: 7-21S-13W
980 feet from N Section Line, 1490 feet from E Section Line
Lease Name: DEBES Well #: 1-7
County: STAFFORD Total Vertical Depth: 3675 feet

Operator License No.: 31160
Op Name: PHILLIPS EXPLORATION COMPANY L.
Address: 1601 SAGEBRUSH
WICHITA, KS 67230

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	225		WITH 225 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/11/2012 6:00 PM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Revd. from: DERBY Company: SOUTHWIND DRILLING, INC. Phone: (620) 564-3800

Proposed Plugging Method: 1ST PLUG AT 3604' WITH 50 SX CMT. 2ND PLUG AT 630' WITH 50 SX CMT. 3RD PLUG AT 240' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: NONE
Date/Time Plugging Completed: 01/11/2012 8:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

Perfs:

1" TO 42' WITH 75 SX CMT. CMT CIRCULATED. 1ST PLUG AT 3604' WITH 50 SX CMT. 2ND PLUG AT 630' WITH 50 SX CMT. 3RD PLUG AT 240' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: DP

District: 01

Signed

Steve Durrant

(TECHNICIAN)

RECEIVED

JAN 25 2012

KCC DODGE CITY

RECEIVED
JAN 27 2012
KCC WICHITA

Form CP-2/3

✓ 1/30/12