

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20955-00-01
Spot: SESW Sec/Twnshp/Rge: 33-33S-30W
720 feet from S Section Line, 1980 feet from W Section Line
Lease Name: WARREN Well #: 1
County: MEADE Total Vertical Depth: 6650 feet

Operator License No.: 9228
Op Name: MARLIN OIL CORPORATION
Address: PO BOX 14630
OKLAHOMA CITY, OK 73113

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5596		WITH 2 SX CMT
CIBP		5710		
CIBP		6070		
SURF	8.625	1535		WITH 650 SX CMT
PROD	4.5	6647	2535	WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/19/2012 10:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: SET CIBP @ 5596' WITH 2 SX CMT. PLUG AT 1560' WITH 50 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 40' FILL TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/19/2012 1:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 5596' WITH 2 SX CMT. 1ST PLUG AT 1560' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 9 SX CMT. CMT CIRCULATED. HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
6216	6220		
6096	6104		
5820	5825		
5807	5811		
5774	5778		
5714	5736		
5632	5642		SPF

Remarks: USED COMMON CEMENT BY SARGENT & LILLARD.

Plugged through: CSG

District: 01

RECEIVED
JAN 24 2012
KCC DODGE CITY

Signed _____
(TECHNICIAN)

RECEIVED
JAN 27 2012
KCC WICHITA