

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-119-20938-00-00  
Spot: SENWSE Sec/Twnshp/Rge: 33-33S-30W  
1650 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: FOX Well #: 1  
County: MEADE Total Vertical Depth: 6623 feet

Operator License No.: 9228  
Op Name: MARLIN OIL CORPORATION  
Address: PO BOX 14630  
OKLAHOMA CITY, OK 73113

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3000		WITH 2 SX CMT
CIBP		3890		
CIBP		5740		
CIBP		6100		
SURF	8.625	1516		WITH 650 SX CMT
DVT		3834		
PROD	4.5	6216	2425	WITH 660 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/12/2012 1:30 PM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: W.R. (DICK) LYNN Company: \_\_\_\_\_ Phone: (405) 478-1900

Proposed Plugging Method: SET CIBP AT 3000', CAP W/CMT. DISPLACE HOLE WITH MUD. CUT OFF 4-1/2" CSG AT 2500'. PLAC CMT PLUGS AS FOLLOWS: 80 SX PLUG AT 1566', 50 SX PLUG AT 700', AND 10 SX PLUG AT 40'. CUT OFF 8-5/8" CSG 4' BELOW GL. WELD ON ID PLATE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: PARTIAL  
Date/Time Plugging Completed: 01/12/2012 5:00 PM KCC Agent: DANIEL BERNASCONI

Actual Plugging Report:

SET CIBP @ 3000' & 2 SX CMT. 1ST PLUG AT 1566' WITH 80 SX CMT. 2ND PLUG AT 700' WITH 49 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5768	5906		
5636	5648		
3058	3770		

RECEIVED  
JAN 27 2012  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

RECEIVED

JAN 23 2012

KCC DODGE CITY

Signed

Daniel Bernasconi  
(TECHNICIAN)

1/30/12