

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-01655-00-01
Spot: E2NENW Sec/Twnshp/Rge: 30-13S-16W
4620 feet from S Section Line, 2970 feet from E Section Line
Lease Name: DREILING OWWO Well #: 1
County: ELLIS Total Vertical Depth: 3559 feet

Operator License No.: 6883
Op Name: ROBINOWITZ OIL COMPANY, A GENE
Address: 4200 E SKELLY DR STE 620
TULSA, OK 74135

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3440		
SURF	8.625	203		135 SX
PROD	4.5	3478		100 SX W/ 450 SX @ 1133'

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/24/2012 2:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: DON DEGENHARDT Company: ROBINOWITZ OIL CO. Phone: (620) 793-2299

Proposed Plugging Method: Ordered- 310 sxs 60/40 poz mix 4 % gel; 500 # hulls
Well was perfed @ 1133' w/450 sxs cement.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/24/2012 5:10 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service R.I.H. with tubing to 3187.42'. Allied rigged to tubing & pumped 100 sxs 60/40 poz with 300 # hulls mixed in.
Pulled tubing to 1650' Allied rigged to tubing & pumped 125 sxs cement with 200 # hulls mixed into circulate cement to surface.
Pulled tubing rigged to 4-1/2" CSG with a swedge & pumped 25 sxs to pressure with 500 # P.I.P. & 300 # S.I.P.
Rigged to 8-5/8" CSG with a swedge & pumped 0 sxs with instant P.I.P. to 150 #.

Perfs:

Top	Bot	Thru	Comments
3429	3431		
3384	3388		
3301	3304		
3256	3260		
3200	3206		

Remarks: ALLIED OIL & GAS LLC TICKET # 34550

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

CM

JAN 25 2012

RECEIVED

JAN 31 2012

KCC WICHITA

Form CP-2/3

2/01/12