

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-01640-00-01  
Spot: E2E2NW Sec/Twnshp/Rge: 30-13S-16W  
3960 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: DREILING OWWO Well #: 2  
County: ELLIS Total Vertical Depth: 3486 feet

Operator License No.: 6883  
Op Name: ROBINOWITZ OIL COMPANY, A GENE  
Address: 4200 E SKELLY DR STE 620  
TULSA, OK 74135

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	217		135 SX
DVT		1113		450 SX
PROD	5.5	3484		150SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/24/2012 9:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Revd. from: DON DEGENHARDT Company: ROBINOWITZ OIL CO. Phone: (620) 793-2299

Proposed Plugging Method: Ordered 425 sxs 60/40 poz 4% Gel; 500 # hulls

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/24/2012 12:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Services R.I.H with tubing to 3187.42'. Allied rigged to tubing & mixed & pumped 150 sxs with 300 # hulls mixed in.  
Express pulled tubing to 1650'. Allied rigged to tubing & pumped 175 sxs with 200 # hulls mixed into circulate cement to surface.  
Pulled tubing rigged to 5-1/2" CSG with a swedge & pumped 25 sxs to pressure with 400 # P.I.P. & 300 # S.I.P.  
Rigged to 8-5/8" pumped 5 sxs cement to pressure with 300 # P.I.P. No shut in pressure blew a small hole in head of well.

Perfs:

Top	Bot	Thru	Comments
3484	3486		ARBUCKLE OPEN
3429	3432		LKC
3231	3234		LKC
3199	3201		TORONTO

Remarks: ALLIED OIL & GAS LLC TICKET # 34549

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

CM

JAN 25 2012

RECEIVED

JAN 31 2012

KCC WICHITA

Form CP-2/3

2/0.1/12