

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21347-00-00
Spot: SEWNWE Sec/Twnshp/Rge: 28-12S-20W
4290 feet from S Section Line, 1650 feet from E Section Line
Lease Name: FLAX Well #: 1
County: ELLIS Total Vertical Depth: 4003 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	272		175 SX
PROD	4.5	3917		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/26/2012 8:30 AM
Plug Co. License No.: 32332 Plug Co. Name: FISCHER PIPE TESTING, INC. DBA FISCHER WELL SERVICE
Proposal Revd. from: GARY WAGNER Company: TENGAS CO. INC. Phone: (785) 735-4124

Proposed Plugging Method: Ordered 350 sxs 60/40 poz, 4% gel, 500 # hulls
1977 CSG perfed @ 1575' w/450sxs cement to surface.
PBTD-3831
CSG leaks-high fluid level

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/26/2012 11:15 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Fischer Well Service R.I.H. with tubing to 3300', Allied rigged to tubing & mixed & pumped 120sxs 60/40 poz mix with 300 # hulls mixed in.
Pulled tubing to 1600' Allied rigged to tubing & mixed & pumped 100 sxs with 200 # hulls mixed into circulate cement to surface.
Fischer pulled tubing, Allied rigged to 4-1/2" CSG with a swedge & valve & pumped 20 sxs to pressure with 300 # PSI & 200 # P.I.P.
8-5/8" CSG was full of cement visual checked.

Perfs:

Top	Bot	Thru	Comments
3821	3831		
3656	3662		
1575			

Remarks: ALLIED OIL & GAS LLC TICKET # 35221

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

CM

JAN 26 2012

RECEIVED
Form CP-2/3

2/01/12 JAN 31 2012

KCC WICHITA