

TO:  
STATE CORPORATION COMMISSIO  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 6720

API Well Number: 15-207-02223-00-00  
Spot: NENENWSW Sec/Twnshp/Rge: 23-23S-13E  
2488 feet from S Section Line, 1297 feet from W Section Line  
Lease Name: AJ HESSLER Well #: 3  
County: WOODSON Total Vertical Depth: 2121 feet

Operator License No.: 6445  
Op Name: MILLER BROS OIL COMPANY, INC.  
Address: 701 W 4TH  
LEBO, KS 66856

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1900		
SURF	8.25	1330		
PROD	4.5	2121		120 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/11/2012 8:00 AM  
Plug Co. License No.: 7719 Plug Co. Name: CHEEVER WELL SERVICE, INC.  
Proposal Rcvd. from: DANIEL HORST Company: \_\_\_\_\_ Phone: (620) 344-1518

Proposed Plugging Method: RUN 2.5 TUBING TO 1700' PUMP 20 SKS. CEMENT. PULL TO 900' PUMP 20 SKS. CEMENT. PULL TO 200' PUMP CEMENT TO SURFACE.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed 01/12/2012 11:00 AM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 1700' pumped 20 sxs cement, pulled tubing to 900' pumped 25 sxs cement, pulled tubing to 150' pumped 200 sxs cement lost circ. Let cement set up till next day ran tubing in hit cement @ 100' pumped 100 sxs cement to surface. casing shot at 900' casing was not pulled, gel spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
1751	1755		MISSISSIPPI

RECEIVED

JAN 23 2012 *MH*

KCC Chanute Dist. #3

RECEIVED

JAN 26 2012

KCC WICHITA

Remarks:

Plugged through: CSG

District: 03

Signed *Michael Heffern*  
(TECHNICIAN)

✓ 2/03/12