

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-23881-00-00
Spot: E2NWNE Sec/Twnshp/Rge: 12-23S-3E
660 feet from N Section Line, 1650 feet from E Section Line
Lease Name: JANZEN Well #: 1
County: BUTLER Total Vertical Depth: 2633 feet

Operator License No.: 33971
Op Name: TRIPower RESOURCES, LLC
Address: BOX 849
ARDMORE, OK 73402

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	220		125 SX
T1	2.375	2453		
PKR		2417		
PROD	5.5	2633		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/27/2012 8:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Revd. from: W B CURRY Company: TRIPower Phone: (580) 226-6700

Proposed Plugging Method: LOAD HOLE WITH SALT WATER. SET CIBP @ 2450' WITH 20' CEMENT ON TOP OF PLUG. CUT 5.5' CASING @ 1450'. PULL 1450' OF CASING. SET CEMENT PLUG FROM 270' TO SURFACE. CUT 4' SURFACE PIPE AND CAP. RESTORE LOCATION.

Plugging Proposal Received By: PATRICK SHIELDS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/27/2012 1:00 PM KCC Agent: DAVID BOLLENBACK

Actual Plugging Report:

PERFS @ 2508'-2518'. SET CIBP @ 2470'. DUMP BAILER W/2SX CEMENT ON TOP OF CIBP. SHOT PIPE @ 1364' - COULD NOT PULL PIPE. PERF 4 HOLES @ 270', BROKE CIRCULATION. CIRCUALTED 100 SX OF 60/40 + 4% GEL TO SURFACE. GOOD CIRCULATION & CEMENT STANDING @ SURFACE. CONSOLIDATED CEMENT TICKET #34060.

Perfs:

Top	Bot	Thru	Comments
2508	2518		MISS


RECEIVED
FEB 01 2012

Remarks:

Plugged through: CSG

District: 02

Signed


(TECHNICIAN)

KCC WICHITA