

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21788-00-00
Spot: W2NWNW Sec/Twnshp/Rge: 12-30S-9W
600 feet from N Section Line, 310 feet from W Section Line
Lease Name: ADELHARDT Well #: 2
County: KINGMAN Total Vertical Depth: 2500 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 912 N LOGAN PO BOX 195
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	237		200 SX
PROD	4.5	2499	1860	100 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/12/2011 11:00 AM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: _____

Proposed Plugging Method: SAND TO 2320 & 4 SKS, 35 SX 1250', 35 SX 900', CIRC 280-0'.

Plugging Proposal Received By: STEVE VANGIESON

Witness Type: PARTIAL

Date/Time Plugging Completed: 12/12/2011 11:00 AM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 2319' AND CAPPED WITH 4 SKS CMT. THE CASING WAS RECOVERED FROM 1860' & PULLED TO 1250', WHERE 35 SX OF CMT WAS SPOTTED. CASING PULLED TO 900', WHERE 35 SX OF CMT WAS SPOTTED. CASING PULLED TO 280', WHERE CMT WAS CIRCD TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2370	2373	CSG	


Remarks: QUALITY WELL SERVICE, 60/40 4% GEL

Plugged through: CSG

RECEIVED
FEB 01 2012
KCC WICHITA

District: 02

Signed



(TECHNICIAN)

2/03/12

VJK