

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-00624-00-00
Spot: SESWNW Sec/Twnshp/Rge: 23-30S-8W
2970 feet from S Section Line, 1270 feet from W Section Line
Lease Name: WEST SPIVEY UNIT Well #: 36
County: KINGMAN Total Vertical Depth: 4310 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	212		125 SX
PROD	5.5	4309	1930	250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/02/2011 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: _____

Proposed Plugging Method: AS PER KCC REQUIREMENTS.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 12/05/2011 6:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4170' & CAPPED WITH 5 SKS CMT. THE CASING WAS RECOVERED FROM 1930' & PULLED TO 1200' WHERE 35 SXS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 700' WHERE 35 SX OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 260', WHERE CMT WAS CIRCD TO SURFACE. TOPPED OFF WITH 37 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4230	4240		CSG

Remarks: QUALITY WELL SERVICE 60/40 4% GEL

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)

RECEIVED
FEB 01 2012
KCC WICHITA

✓ 2/03/12

JK