

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-21010-00-01
Spot: W2NWNW Sec/Twnshp/Rge: 33-25S-5E
4578 feet from S Section Line, 5225 feet from E Section Line
Lease Name: PIERPOINT A Well #: 110
County: BUTLER Total Vertical Depth: 2150 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.62	244		175 SX CMT
PROD	5.5	823		225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/11/2012 8:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 655-1997

Proposed Plugging Method: PER KCC DISTRICT #2 RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/11/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 625', CONSOLIDATED WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 85 SXS CLASSA COMMON 3% GEL, 2% CC TO SURFACE. CEMENT CIRCULATED. LAYED DOWN TUBING. SWEDGED INTO 5-1/2" CASING & SQUEEZED CEMENT ON BACKSIDE, SHUT IN PRESSURE @ 400#. PLUG DOWN 5:00 P.M., 1-11-2012. CONSOLIDATED OILWELL SERVICES TICKET #34144.

Perfs:

Top	Bot	Thru	Comments
600	615	CSG	ADMIRE

Remarks: COMPLIANCE / DENIED TA

Plugged through: TBG

RECEIVED

FEB 03 2012

KCC WICHITA

District: 02

Signed

Duane Krueger

(TECHNICIAN)

2/08/12

JK