

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19647-00-00
Spot: SEnwSE Sec/Twnshp/Rge: 21-25S-5E
1756 feet from S Section Line, 1791 feet from E Section Line
Lease Name: CHESNEY A Well #: 199
County: BUTLER Total Vertical Depth: 1475 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	1467		365 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/11/2012 8:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 655-1997

Proposed Plugging Method: PER KCC DISTRICT #2 RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER
Date/Time Plugging Completed: 01/11/2012 5:00 PM

Witness Type: COMPLETE (100%)
KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 850', CONSOLIDATED WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 115 SXS CLASS A COMMON 3% GEL, 2% CC TO SURFACE. CEMENT CIRCULATED. LAYED DOWN TUBING. SWEDGED INTO 5-1/2" CASING & SQUEEZED CEMENT ON BACKSIDE, SHUT IN PRESSURE @ 400#. PLUG DOWN 5:00 PM., 1-11-2012. CONSOLIDATED OILWELL SERVICES TICKET #34146.

Perfs:

Top	Bot	Thru	Comments
1455	1460	CSG	DOUGLAS
870	894		WHITE CLOUD
866	870	CSG	WHITE CLOUD
830	846	CSG	WHITE CLOUD

Remarks: COMPLIANCE/DENIED TA

Plugged through: TBG

RECEIVED

FEB 03 2012

KCC WICHITA

District: 02

Signed _____

Duane Krueger
(TECHNICIAN)

Form CP-2/3

2/08/12

JK