

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-22896-00-00  
Spot: NWNWSWSW Sec/Twnshp/Rge: 32-33S-6E  
1255 feet from S Section Line, 4979 feet from E Section Line  
Lease Name: BERRY Well #: 11  
County: COWLEY Total Vertical Depth: 3100 feet

Operator License No.: 34470  
Op Name: VICTORY MINERALS LLC  
Address: PO BOX 414931  
KANSAS CITY, MO 64141

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	200		100 SX
PROD	4.5	3090		100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/17/2012 8:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: CARMON DECKER Company: VICTORY MINERALS LLC Phone: (816) 223-3712

Proposed Plugging Method: AS PER KCC DISTRICT #2 RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 01/18/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

JUNK IN HOLE, RIH ON WIRELINE SET CIBP @ 360'. RIH ON WIRELINE PERFORATED SQUEEZE HOLES @ 350'-351'. RIH WITH TBG @ 355', GRESSELL OILFIELD SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 125 SXS @ 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED INSIDE & ON BACKSIDE OF 4-1/2" CASING. PLUG DOWN 11:30 AM 1-18-2012. GRESSEL OILFIELD CEMENT TICKET #38861.


Perfs:

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed

  
(TECHNICIAN)

RECEIVED  
FEB 03 2012  
KCC WICHITA

2/03/12

✓